



RACINE COUNTY
UBLIC WORKS & DEVELOPMENT SERIVCE
14200 WASHINGTON AVENUE
STURTEVANT, WI 53177-1253

County Trunk Highway "K" Project Flyer



2022 Resurfacing

Racine County will resurface County Trunk Highway "K" (Apple Rd)

The Contractor plans to begin work on June 6, 2022. It may take 4-8 weeks to complete this project.

Check inside for details.

Project Overview

Traffic Control

Racine County will maintain access for local-traffic during the course of this project. Through-traffic will follow a well-signed detour route to bypass the project area. See the enclosed detour map for more information. Motorists may use highway "K" to access the homes and businesses within the project area. The Contractor will work to maintain services including postal, sanitation, and school bussing. Of course, motorists should budget more travel time to allow for minor delays.

Preparatory Work

Racine County will begin work on the project by placing stakes near some of the construction areas. These stakes stand outside of the construction area and help guide the workers. With the stakes in place, Workers can begin replacing corroded drainage pipes beneath the highway and intersecting roads. The Contractor will also make small improvements to the base material supporting the pavement at cross-road intersections. This preparatory work will occur within the County highway right-of-way and will

Road-base preparation

The Contractor will begin this phase of the project by sawing the pavement at the boundaries of the work area. When the sawing is complete, machines will break-up, shape and compact the existing asphalt pavement and underlying base material. This new base will provide a strong, smooth support for the first layer of new asphalt pavement. The Contractor will maintain the existing road alignment. Expect small changes near cross-road intersections.

Pavement

When the road base is complete, the Contractor will place the first layer of asphalt pavement. To improve safety and reduce long-term maintenance costs, pavement will include a 3-footwide paved shoulder on highway "K". After the completion of the first layer of pavement, the Contractor will place gravel shoulder material along the highway edges.

Completion

After shouldering, the Contractor will lay the final course of pavement including the replacement of asphalt driveway approaches and cross-road intersections. Racine County surveyed the existing driveway pavement so that the Contractor can restore asphalt driveway approaches to their original shape and position. As Workers complete the final layer of asphalt pavement, they will replace the gravel driveway approaches and shoulders. At this stage, the Contractor will apply fresh pavement markings on the new asphalt surface.

Information

During weekdays from 8 A.M. to 4:30 P.M., to report an urgent project concern, provide suggestions or request more information, contact Racine County Public Works and Development Services by dialing (262)886-8440.